

## Two way FRR — steel frame

Specification number	Performance	Specifications
<b>GBS 120</b>	<b>FRR</b> -/120/120	<b>Lining</b> 1 layer 19mm GIB Fyrelite® each side
	<b>STC</b> 42	<b>LB/NLB</b> Non load bearing
	<b>Rw</b> 42	

### FRAMING AND WALL HEIGHT

Minimum steel stud dimensions to be 92 x 34 x 0.75mm nominal with a 6mm return.

Minimum steel channel dimensions to be 92 x 30 x 0.75mm nominal for the bottom channel and 92 x 50 x 0.75mm nominal for the top channel.

Top and bottom channels are fixed to the floor and ceiling in true alignment.

Stud spacing at 600mm centres maximum.

Place studs to allow the nominated expansion gap at the top of the frame.

The studs are held in place by the “grip” of the channels.

#### Recommended maximum wall height

Note that maximum wall heights for fire rated systems can be lower than what can be achieved with non-fire rated construction.

Nominal stud dimension (mm)	BMT (mm)	Stud centres (mm)	Max wall height (mm)	Expansion at top of studs (mm)
92 x 34	0.75	600	3000	15
		400	3400	15
150 x 34	0.75	600	4400	20*
		400	5000	25*
	1.15	600	5000	25*
		400	5700	30*

\*Use a minimum 50mm-deep head channel.

### LINING

1 layer of 19mm GIB Fyrelite® each side of the frame.

Vertical fixing only permitted. Full height sheets shall be used where possible.

When sheet end butt joints are unavoidable, they shall be formed over nogs and staggered.

Offset joints between sheets on opposite sides of the frame.

Sheets shall be touch fitted.

All sheet joints must be formed over framing.

Linings are installed hard to floor.

### FASTENING THE LINING

#### Fasteners

32mm x 6g GIB® Grabber® Self Tapping Drywall Screws.

#### Fastener centres

300mm centres up each stud.

Place fasteners 12mm from longitudinal sheet edges and 50mm from sheet ends.

Place fasteners at 200mm centres along sheet end butt joints.

Fastening the linings at 18mm from sheet ends to top and bottom channels is permitted as long as the fasteners do not connect the studs and channels. Do not fix linings to the top track when floor deflection has to be accommodated.

### SERVICES

Holes may be drilled or pre-punched in the metal studs to allow installation of electrical service lines and plumbing supply pipes.

### JOINTING

All screw heads stopped and all sheet joints tape reinforced and stopped in accordance with the publication entitled “GIB® Site Guide”.

